



**WASHTENAW COUNTY  
FINANCE DEPARTMENT**

**Purchasing Division**

P. O. Box 8645, 220 N. Main, Ann Arbor, MI 48107-8645  
Phone (734) 222-6760, Fax (734) 222-6764  
www.purchasing.ewashtenaw.org

September 22, 2015

**Addendum #1**

**RFP No.** 6853  
**Title:** RIVER RAISIN BANK RE-STABILIZATION AT SHARON MILLS COUNTY PARK  
**Due Date:** FRIDAY SEPTEMBER 25, 2015 at 2:00PM

This addendum is generated to clarify the items identified below and shall become part RFP 6853. Acknowledgement of receipt of this addendum by the bidder must be recorded on page P-1 in Proposal Section of the submitted bid document. Failure to submit acknowledgement of receipt of addendum will result in disqualification of bid.

**Replace Table of Contents – Part II: DETAILED SPECIFICATIONS DIVISION 1 and 2** with the following:

**Division 1 - GENERAL REQUIREMENTS**

**Pages 1 - 15**  
(starts on page)

Summary of Work	2
Site General Provisions	3
Method of Measurement and Basis of Payment	4
Project Meetings	9
Submittals	10
Regulatory Requirements	13
Quality Control	14

**Division 2 – SITE WORK**

**Pages 1 - 10**  
(starts on page)

Earthwork	2
Armoring	4
Topsoil	6
Seeding	8

**For Clarification:**

1. An existing 7" Crabapple tree at the top of slope, south of the flagpole shall be removed. This removal to include roots and shall be incidental to other project work.
2. The existing concrete ramp driveway has a cross-section of a 6" thickness (reinforced) on 4" deep compacted Class II granular material. The CONTRACTOR must use all necessary measures/procedures to protect this area from damage during execution of work. (incidental to Site Services work).
3. Note 8 on page 3 of 4 in the drawing set states " Surplus excavated materials are to be relocated elsewhere on-site...". The CONTRACTOR may temporarily stockpile excavated material at OWNER's property off of Bethel Church Road, roughly one-half mile from project site. These materials will need to be permanently removed by CONTRACTOR and lawfully disposed of off-site before completion of the project work. *(THIS IS A DIFFERENT DIRECTIVE THAN GIVEN AT PRE-BID MTG).*
4. "**ARMORING**" - New stone materials used in the armoring below elevation 901 may be rounded, natural bank-run stone. All bank armoring above elevation 901 shall match existing split stone appearance.
5. Fees for required permits of the MDEQ and Washtenaw County Road Commission (WCRC) will be paid for by the OWNER. Payment to the CONTRACTOR for work within the road right-of-way may be held by OWNER until work is approved by WCRC. The SESC application, inspections, and permit fees are the responsibility of the CONTRACTOR.

**END OF ADDENDUM #1**

***Beth A. Duffy, CPPB***  
***Senior Buyer***

cc: RFP 6853